


TRENCH DETAIL



INSTALLATION WITHOUT TRENCHING

NOTES:

1. SILT FENCE SHALL BE PLACED ON SLOPE
CONTOURS TO MAXIMIZE PONDING EFFICIENCY.

2. INSPECT AND REPAIR FENCE AFTER EACH
STORM EVENT AND REMOVE SEDIMENT WHEN
NECESSARY. 9" (225mm) MAXIMUM
RECOMMENDED STORAGE HEIGHT.

3. REMOVED SEDIMENT SHALL BE DEPOSITED
TO AN AREA THAT WILL NOT CONTRIBUTE
SEDIMENT OFF-SITE AND CAN BE PERMANENTLY
STABILIZED.

NOT TO SCALE

SILT FENCE